



Technical specifications:

20'x8'x9'6" MODULAR UNIT / ACCOMMODATION CONTAINER

Introducing our MH 101 – 100mm walls Modular Unit / Accommodation Container.

A solid, adaptable, and robust solution for your spatial needs.

key features

Dimensions: A spacious 20' x 8' x 9'6" unit, designed to ISO Standard 1161, with a tare weight of 2200 Kg. The container offers ample internal dimensions: 5.771m length, 2.151m width, and 2.51m height.

Design Flexibility: Our modular design allows for unlimited compounding of units in longitudinal and transverse directions, and up to 3 floors in height.

Portability: Can be delivered assembled or as flat pack kits for convenience and ease of transport.

structural specifications

Steel Framework: Crafted from cold-formed steel profiles, finished with corrosion-resistant electrophoresis, galvanizing primer, and super weather-resistant paint.

Floor Composition: A sturdy structure featuring galvanized steel sheet metal, noncombustible mineral wool insulation, CCA boards, and a PVC flooring covering.

Ceiling Composition: Resilient corrugated "ISO" Roof, insulated with noncombustible mineral wool sandwich panels, and equipped with meteor water outlets for efficient drainage.

Façade Side Walls: Comprised of interchangeable mineral wool panels, with a fire rating of 60 minutes according to BS 476.

Doors & Windows: Standard external aluminium door with pre-painted aluminium frame, and PVC tilt and swing windows equipped with aluminium rolling shutters.

contact us

+44 (0)1298 79753

info@jackson-group.co.uk

T F Jackson Accommodation Limited, Harpur Hill Industrial Park, Buxton, Derbyshire, SK17 9JL

www.jackson-group.co.uk





Technical specifications:

20'x8'x9'6" MODULAR UNIT / ACCOMMODATION CONTAINER

additional features

Standard Colour: A sophisticated grey-white steel construction (RAL 9002), with doors and windows in a contrasting white.

Electrical Installations: Compliant with CE standards, featuring a suitable connection plug/socket, an inner distribution system, protective current switch, and automatic fuses.

Fittings include LED strip lights, light switch, power sockets, and USB ports.

Certification: All dimensions, weight, payload, and stacking are RINA Certified, with certificates available for components.

delivery options

Units can be delivered in various configurations - in bundles of 3 x 20' kits or 4 x 20' kits, or assembled (for local deliveries only).

warranty

Enjoy peace of mind with a 1-year warranty on all components and paint.

Experience the innovative design and superior quality of our MH 101 – 100mm walls Modular Unit / Accommodation Container. Transform your space with T F Jackson Portable Accommodation Ltd.

Note: Rights to technical changes are reserved.

